BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Modified SCHDULE-B

Name of Work: Improvements and Construction of CC Roads and Drainage Works Bhuvaneshwari nagara 1st Main 1st, 2nd, 3rd & 4th cross Muneshwara Badavane Shivaraj house in Back side of Market in Dasarahalli ward No:15

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4.00	5	6
1	Earthwork excavation by manual means in ordinary soil involving an avegage horizontal throw up to 2 meters and an average lift up to 0.5 m, excavated surface leveled and sides neatly dressed the diposed earth to be levelled neatly after breaking of clods complete as per specifications	Cum	284.50	73.37	Rupees Seventy three and Thirty seven Paise Only
2	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of Machinery, screed Vibratory, Power Floater, blade and disc etc., with all lead and lift	Sqm	2441.92	80.53	Rupees Eighty & Fifty three Paise Only
3	Providing Concrete Groove cutting for width of 5mm to 10mm and depth 80mm100mm including cost of cutting machine generator & HOM of machinery, including cost of blade coolant etc., including cleaning of groove & Providing sand and hot bitumen fillars, and fillars metal etc., including cost of conveyance of all materials, labour lead and lift charges and all other incidental charges as per drawing and as per specifications.	rmt	161.50	102.90	Rupees One Hundread Two & Ninety paise Only
4	Earthwork excavation for foundation of buildings, water supply, sanitary, lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	77.09	234.87	Rupees Two Hundread Thirty four and Eighty Seven Paise Only
5	Removing B.S.Slab of drain and stacking etc., complete Qty Executed upto 125%	Sqm	33.75	51.90	Rupees Fifty One & Ninety Paise Only
	Qty Executed above 125%		769.77	55.47	Rupees Fifty five & Forty Seven Paise Only
6	Refixing stone slabs of drains and pointing in CM 1:3 etc complete Qty Executed upto 125%	Sqm	20.25	64.22	Rupees Sixty four & Twenty two Paise Only
	Qty Executed above 125%		783.27	68.00	Rupees Sixty eight Only

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-73

7	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	77.09	4130.00	Rupees Four Thousand One Hundread Thirty Only
8	Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement design mix M30 at 360 kg per cum, with 25mm and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates @ 0.46 cum with superplastizer at 3lts conforming to IS 9103-1999 reaffirmed 2008. coarse and fine aggregate conforming to IS:383, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of .. contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing, compound, finishing to lines and grades as per drawing complete as per specifications.	Cum	400.20	5655.33	Rupees Five Thousand Six Hundread Fifty five & Thirty three Paise Only
9	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69cum and fine aggregates @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5.20	4880.35	Rupees Four Thousand eight Hundread Eighty & Thirty five Paise Only
10	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specifications.	Sqm	22.68	328.99	Rupees Three Hundread Twenty eight and ninety nine Paise Only
11	Providing T.M.T. steel reinforcement for R.C.C. work including straightening cutting, bending, hooking, placing in position, lapping and (or welding wherever required, trying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	ton	14.27	57430.36	Rupees Fifty seven Thousand four Hundread Thirty & thirty six Paise Only

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-73.

12	Supplying and fixing precast rainforced concrete slab 10cm thick including cost of reinforcement as pwe design and drawing materials cost, tranportion hire charges of machinary, machine cutting the verticale face to get plain even surface ctc. Complete with all leads and lift convetyenc charges labour charges inclusive cost of all materials Qty Executed upto 125%	Sqm	45.00	1303.20	Rupees One Thousand three Hundread three & Twenty Paise Only
	Qty Executed above 125%		52.20	1350.56	Rupees One Thousand three Hundread Fifty & Fifty six Only
13	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km	Cum	272.88	63.73	Rupees Sixty three & Seventy Three Paise Only
	Qty Executed above 125%		88.71	68.20	Rupees Sixty eight & Twenty Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-73.